

PARKING AT FINANCE OFFICE

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL KSH
A	Excavate oversite average 200mm deep and cart away	300	sm		
B	300mm thick approved hardcore fill well compacted	300	sm		
C	Allow for compacting and levelling surfaces	300	sm		
D	50mm thick murrum blinding	300	sm		
E	Compact hardcore with 8 ton roller	300	sm		
F	80mm thick heavy duty precast concrete paving blocks (cabro blocks or equivalent) on and including 50mm thick sand bed, laid to approved pattern all as per manufacturer's approval	300	sm		
	KERBS:-				
G	125 x 250mm pre-cast concrete class 25 half nattered (kerb, jointed and pointed in cement in cement and sand (1:3) mortar laid on and including 250 x 100mm plain concrete class 20 foundation and haunching at back including excavation and disposal	25	Lm		
	TOTAL CARRIED TO COLLECTION				

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL KSH
A	<p><u>Landscaping</u></p> <p>Plant the following including providing all plants or seeds and growing in nursery until of sufficient maturity to transplant</p> <p>Excavate and prepare surface to plant grass</p>	204	sm		
B	Supply and spread approved manure to ground surfaces	204	sm		
C	Plant grass and flowers to manured surfaces and water seedlings until well established	204	sm		
	<p>Carried to collection below</p> <p style="text-align: center;"><u>COLLECTION</u></p> <p>Total from Page 1</p> <p>Total from above</p>				
	TOTAL OF PARKING CARRIED TO SUMMARY				