

BILL OF QUANTITIES					
Rehabilitation Rahai Baghau Rong'e Road					
ITEM	DESCRIPTION	UNIT	QUANTITY	RATE (KSHs)	AMOUNT (KSHs)
1.1.1	Bill No. 1 Erection and maintenance of project sign board as per engineers sample	ITEM	1		
2.1.1	Bill No. 2 Concrete and Culvert works Provide and install 900mm culverts encased in concrete class 20/20 including all formwork, as per engineers specifications	M	32		
Bill no 3 Concrete Slab strips of 1.5m for a length 300m and Drifts of 20m x7m wide					
2.1.2	Masonry headwalls to culverts	SM	12.5		
2.1.3	Prepare to fill hardcore to receive concrete	CM	495		
2.1.4	BRC A142 fabric mesh reinforcemt	SM	990		
2.1.5	Provide, place and compact/ vibrate concrete class 20/20 ratio 1:2:4 to a thickness of 150mm	CM	148.5		
3.1.1	Bill No. 4 Grading and Gravelling works Prepare to light grade the road with drainage provisions	SM	17,600		
				Total Sum	-
4	Provide for a 6 % of the Total sum as a provision for supervision.	%			-
				SUB-TOTAL	-

Add 16% VAT	-
-------------	---

GRAND TOTAL	-
-------------	---